

Subbase Drydock

T: [REDACTED] Fax: [REDACTED]
 [REDACTED] Box 304429
 St. Thomas, USVI 00803

Estimate

Date	Estimate #
8/31/2017	915

Name / Address
LSJ,LLC "Big N" Anna: [REDACTED] [REDACTED]

Terms	Project
Upon Comple...	

Description	Qty	Cost	Total
Sandsweep cargo bay, cargo bay walls, and aft deck. Prime and paint with a non-skid two part epoxy paint. Includes Labor and Materials.	1	12,340.00	12,340.00
Fabricate and weld splash guards into place to minimize water intrusion through the front ramp. Prime and paint for increased longevity.	1	7,500.00	7,500.00
Prep and grind cracks throughout vessel. Includes Labor and Materials.			
Both cutless bearings are worn and not within tolerance. We recommend changing these while hauled out. We also recommend checking the engine alignment while hauled out to ensure there are no issues with the drive train. Includes Labor and Materials.	1	3,750.00	3,750.00
Degrease engine room, remove, clean and dispose of all waste oil. Approximately 200 gallons of waste oil after clean up.	1	3,750.00	3,750.00
	Total		\$27,340.00

Signature _____