

# Estimate

B.V.I. Painters Ltd  
P.O. Box 824,  
Road Town, Tortola  
British Virgin Islands.  
Tel: 284 494 4365

Name/Address
Little C Carlos Rodriquez St. Thomas

Date	Estimate No.	Project
02/25/17	2895	

Item	Description	Quantity	Cost	Total
Labour and Material	Labour and Material for Topside, Deck and cabin house Topside Paint job include 1.Grind out bad Spots 2.Fill where needed with west System Epoxy 407 filler 3.Sand and Fair area 4.Sand intire topside 5.Tape amd Mask 6.Spray two coats of Primer 7.Sand Primer 8.Change Tape 9.Spray four coats of paint 10.Sand Paint 11.Spray two coats of clear		5,400.00	5,400.00
Labour and Material	Labour and Material for deck and Cabin house  Deck and Cabin house Job include same as Topside excluding clear coat		9,900.00	9,900.00
	upper deck Stiplin will remain the same lower deck paint with Non Skid Cabin house top will be spray with Non Skid Overhead will stay textured		0.00	0.00
Labour and Material	Labour and Material for the Bottom  Sand and Paint		1,200.00	1,200.00
			<b>Total</b>	

# Estimate

B.V.I. Painters Ltd  
P.O. Box 824,  
Road Town, Tortola  
British Virgin Islands.  
Tel: 284 494 4365

Name/Address

Little C  
Carlos Rodriquez  
St. Thomas

Date	Estimate No.	Project
02/25/17	2895	

Item	Description	Quantity	Cost	Total
	Sherwin Williams Paint will be used for the bottom  Note : We will remove the Rob Rail and Inspect if there is anything unusual in our findings we will call to inform and there will be an extra charge.			
			Total	\$16,500.00