



# Fax



Bill W. Whaley, C.P.G.  
Hydrogeologist, Vice President

<b>To:</b> Brice - Cypress, Inc.	<b>From:</b> Bill W. Whaley
<b>Phone:</b>	<b>Pages:</b> 2
<b>Fax:</b> [Redacted]	<b>Date:</b> 8/13/2012
<b>Re:</b>	<b>CC:</b>
<input type="checkbox"/> <b>Urgent</b> <input checked="" type="checkbox"/> <b>For Review</b> <input type="checkbox"/> <b>Please Comment</b> <input type="checkbox"/> <b>Please Reply</b> <input type="checkbox"/> <b>Please Recycle</b>	

Sincerely,

Bill W. Whaley, C.P.G.  
 Hydrogeologist  
 Vice President  
 HydroGeologic Services, Inc.  
 P.O. Box 94716  
 Albuquerque, NM 87199-4716

[Redacted] Fax [Redacted]  
 NM License No. [Redacted]

P.O. Box 94716, Albuquerque, NM 87199-4716 [Redacted] Fax [Redacted]  
 New Mexico License No. [Redacted]  
 We Do Water Well

REQUEST FOR BIDS

CYPRESS, INC.

PRODUCTION WELL (6-INCH CASING)

The bidder hereby proposes to furnish all equipment, material and labor, and to do all the work required to complete the work in accordance with specifications for the unit prices, lump sum, or hourly rates set forth below and in the attachments. If needed, attach additional pages to provide further detail on bid items.

Item	Estimated Quantity	Units	Unit Price	Total Price
1 Mobilization, Demobilization and Clean-Up	1	Each	5,500.00	5,500.00
2 Install Cemented Surface Casing to Minimum 40 Foot Depth	1	Each	4,900.00	4,900.00
3 Drill Minimum 10 3/4-inch Hole	800	Feet	37.00	29,600.00
4 Furnish and Install 6-inch Inside Diameter Blank PVC Casing	400	Feet	16.00	6,400.00
5 Furnish and install 6-Inch Inside Diameter PVC Screen	400	Feet	20.00	8,000.00
6 Furnish and Install Pitless Adapter	1	Each	4,650.00	4,650.00
7 Furnish and Install Formation Stabilizer	1	Each	11,950.00	11,950.00
8 Furnish and Install Annular Seals and Backfill	1	Each	4,500.00	4,500.00
9 Well Development	16	Hours	400.00	6,400.00
10 Well Testing	24	Hours	210.00	5,040.00
11 Wellhead Seal and Protection	1	Each	815.00	815.00
12 Stand-By Time	8	Hours	250.00	2,000.00
***13 Furnish and Install Permanent Pump and Controls	1	Each	21,246.00	21,246.00
***20 HP/100 GPM pump set @ 504' on 2" galv. drop pipe w/control panel		Total		110,996.00

(7170.00 if use 3/4 P. gravel)

\$ 163,826

HydroGeologic Services, Inc.

NM License No