



Bryan's Electrical Contracting Corp.

Licensed Electrical Contractor

Residential.Commercial.Industrial.Electrical Wiring & Installation



September 22, 2016

To: Mr. Hugo Hodge Jr.

Re: Great St. James Proposal

We Propose the following materials to complete the Great St. James Project

RISER POLE: \$54,900.00

- 2 EACH RMVI321156AB6CS1392 RISER POLE MOLDED VACCUM INTERRUPTER
Riser Pole Molded Vacuum Interrupter, Three-Phase, 15kV,
600 Amp Termination, Air Bushings (for Riser Pole Units),
with Customer Specific Modifications

METERING OPTION 1 :\$47,600.00

- 1 PMDF-315-F499-L9-200-LB1
15KV, 95KV BIL, Three-Phase, Dead-Front, Air Insulated, Primary Metering Cabinet for
Loop Feed. Included are the following items installed and pre-wired to a terminal block:
F499 - Type 304L stainless-steel cabinet (enclosure, roof and doors only)
6 - 200 Amp Bushing wells on the line side (two (2) per phase)
3 - 200 Amp Bushing wells on the load side (one (1) per phase)
1- 10 Pole test switch
1- 13 Terminal, stainless steel, meter socket with test switch provisions
3 - 66:5 Outdoor style, non-fused, potential transformers
3 - 200:5 Outdoor style, current transformers
9 - Load-break inserts

METERING OPTION 2: \$47,600.00

- 1 EACH Stainless Steel 600 Amp, Pad-Mounted
Dead-Front Metering Cabinet, NEMA 3R
Weatherproof Outdoor Construction.
SPS-DFPM3152122-SS
2 EACH Adder Lot Bushing Well Inserts (Qty 9)

SWITCH GEAR MANUAL OPTION: \$138,490.00

- 2 EACH 65152R1- A10C3E2L71 S&C
VOLTS: 14400 AMPERES: 600
PAD-MOUNTED GEAR -- OUTDOOR PRIMARY
DISTRIBUTION -- MANUAL MODEL PME-12
A10-STAINLESS STEEL ENCLOSURE OLIVE GREEN
C3-KEY INTERLOCK
E2-FUSE STORAGE COMPARTMENT #2 L71-INTERNATIONAL CRATING



Bryan's Electrical Contracting Corp.

Licensed Electrical Contractor

Residential.Commercial.Industrial.Electrical Wiring & Installation

Denny Bryan

- | | | | |
|----|------|----------|---|
| 18 | EACH | 3093-MEG | S & C SWITCHGEAR
S&C POWER FUSE - TYPE SME-20 INDOOR
DISTRIBUTION - FUSE UNIT END FITTINGS (INCLUDING
SILENCER) FOR USE WITH SMU-20
9 END FITTINGS FOR THE UNIT AND 9 EXTRA |
| 18 | EACH | FUSES | S & C FUSES
FUSE UNITS/REFILLS 14.4KV (AMPERE RATING,
CATALOG NUMBER AND TCC TO BE ADVISED BY
CUSTOMER)
9 FUSES FOR THE UNIT AND 9 EXTRA |
| 1 | EACH | 9931-074 | S&C, PENTAHEAD SOCKET |

Regards,

Denny Bryan
President