



**Atlanta Refrigeration Service VI**  
7350 Estate Bovoni, Suite 121C, St. Thomas USVI 00802

# QUOTE

*Approved*

<b>Job Location</b> Little Saint James Little Saint James St. Thomas, VI 00802 Tel.: Fax:	<b>Quote Information</b> Date: Aug 23, 2010 ARS Quote ID#: 8371667 Submitted By: Sean Dillon Original ARS Inv#: Submitted To: Bill Rowles Original Call Date: 8/23/2010
---	---

We Submit Specific and Estimations for the Listed Below:

Equipment: Split-System (Ductless) Manufacturer: Sanyo	Model #: Serial #:
---	-----------------------

**Description of Work Required:**  
The following is a quote for 7 new Sanyo mini split systems. While on site for a recent inspection of equipment it was found that the office a/c has no controller on it and is running on default setting with no temp control. The current units are generic and new controllers can't be ordered. One of the other lower rooms are also missing a controller. The cupola room has a bad fan motor that sounds like the bearing are going bad on it. Unit will need to be replaced in the near future. Master bedroom on second level also has a motor bearing that is intermittently going bad and will need to be replaced. Room next to it is also missing controller and feels low on refrigerant. The two lower bedrooms don't have a/c and will have new units installed. Condensing unit's fan covers are falling off and all units are rusted out on the bottom. All units in this quote will be high efficiency units. This quote includes all equipment, materials, and labor required for installation. Once finished with the installation the technician will test the units to ensure proper operation. Any additional work outside the scope of this quote will be billed separately. Thank you for choosing Atlanta Refrigeration Service VI. "Your Single Source Responsibility."

Materials		
Description	Qty	Total
1.5 Ton Sanyo Mini-Split System	2.0	\$4,589.70
1 Ton Sanyo Mini-Split System	5.0	\$8,407.35
Copper Line Set & Insulation	1.0	\$568.41
Electrical Supplies	1.0	\$338.69
Refrigerant	1.0	\$350.00
Condensor Wall Mount	7.0	\$525.00
Misc Installation Supplies	1.0	\$280.00

Labor		
Description	Qty	Total
Advanced Technician1 Labor	1.0	\$3,040.00
Advanced Technician2 Labor	1.0	\$3,040.00

<b>Important Notes:</b> Lead time is contingent upon quote approval and availability of parts. Customer is responsible for shipping charges, duty, taxes, and any customs charges unless otherwise stated in the quote.	<b>Total Materials:</b>	\$15,059.15
	<b>Total</b>	
	<b>Total Misc./Welding:</b>	
	<b>Total Labor:</b>	\$6,080.00
	<b>Initial Call:</b>	
	<b>Shipping/Freight:</b>	
<b>Warranty Information:</b> Standard Manufacturer warranty and 90 days labor warranty from ARS USVI if parts are installed by ARS USVI. QUOTE IS VALID FOR 15 BUSINESS DAYS FROM ISSUE DATE.	<b>Subtotal:</b>	\$21,139.15
	<b>Tax:</b>	
	<b>Total:</b>	\$21,139.15
	FAX BACK SIGNED TO 340-775-9122	

<b>Authorization</b>	
Client Authorization: _____	ARS Acceptance: _____

We reserve right to correct any material errors contained herein. Quote valid for 30 days unless otherwise specified. If parts are returned, a minimum of 25% restocking fee may apply. Payment due at completion of work unless other arrangements have been made.