



ROOF CONSTRUCTION NOTE "W"
 METAL CORRUGATED GAUGE GALVANIZED, CORRUGATED STEEL SHEETS FASTENED TO (FLAT) WOOD PURLINS WITH #8 X2" WOOD SCREWS. FASTEN EVERY THIRD CORRUGATION (8" O.C.) @ EACH PURLIN. END LAPS TO BE 6" CENTERED OVER A PURLIN. SIDE LAPS TO BE 1 1/2" CORRUGATIONS FASTENED WITH #8 X 1 1/2" SELF TAPPING SHEET METAL SCREWS @ 8" O.C. ALL SCREWS TO HAVE A MIN. 1/2" DIA. HEAD & A NEOPRENE WASHER.
 ATTACH PURLINS THRU PLYWOOD DECKING (OR EQUAL) TO RAFTERS WITH 2-#6 X 3 1/2" WOOD SCREWS. COUNTERSINK PURLINS & DRILL 3/16" DIA. HOLE THRU PURLIN & PLYWOOD. DRILL 3/32" DIA. LEAD HOLE INTO THE RAFTER.
 MATCH FELT PAPER, PURLINS, INSULATION & ROOFING WITH EXISTING

KITCHEN RENOVATION
 LITTLE ST. JAMES
 U.S. VIRGIN ISLANDS

PROPOSED ROOF PLAN AND NOTES

REVISIONS	

DRAWN BY:	O.C.
CHECKED BY:	deJONGH
SCALE:	1/4" = 1'-0"
DATE:	
JOB NO:	2008.21
SHEET:	