



B.V.I. Painters Ltd
 P.O. Box 824,
 Road Town, Tortola
 British Virgin Islands.
 Tel: [REDACTED]

Estimate

Date	Estimate No.
02/22/19	3122

Name/Address
Calypso 34ft Little saint James

Description	Quantity	Cost	Total
Labour and Material cost estimate		0.00	0.00
1.) Topside . Sand entire topside with long Board . Fill and fair . Tape and mask . Spray two coats of primer . Sand Primer . Change masking tape . Spray four coats Awlgrip topcoat colours (Owner Choice) . Sand colours and spray 2 coats of high solid clear coat.		3,400.00	3,400.00
2.) Deck . Grind out all bad spot . Re-Laminate using west system epoxy with chopped matt 1.5oz and Biaxle 1708 . Sand entire deck . Fill and Fair . Tape and Mask . Spray two coats of primer . Sand Primer . Apply four coats of Top coats . Tape off smooth areas and apply two coats in non-skid area with silicone beads		4,000.00	4,000.00
Please note this is only an estimate base on the pictures submitted			
50% deposit before start balance due on completion.			
		Total	\$7,400.00