

Estimate

Pool Sharks Pools & Spas
 8168 Crown Bay Marina #505
 St. Thomas U.S.V.I. 00802

 (Office)
 (Cell)

Name/Address
Kyle Reavis Little St. James

Date	Estimate No.	Project
08/11/18	199	

Item	Description	Quantity	Cost	Total
Resurface	This estimate is for the "Flag Pole Pool" - West End of Island:		65,000.00	65,000.00
Manual Labor	Remove scumline tile .. 6" x 192'			
Manual Labor	Remove any hollow/delaminated pool surface plaster (if excessive delamination, additional labor costs may be expected)			
Manual Labor	Pressure wash pool & prep for tile setting and plastering			
Technical Labor	Set new 6" tile and epoxy grout (cost of tile & epoxy grout not included)			
Technical Labor	Apply bond-kote for pool plaster			
Resurface	Apply pool plaster & sealer			
Misc	This estimate is for applying a sealer to the finished plaster... should you elect to not use the sealer, there will be an extra charge for (1) a tank & disposal of the toxic run off water from the acid washing process, as well as (2) the traditional 21 day curing process.			
Misc	Debris Removal / Dumpster .. additional charge dependent on what needs to be removed			
Misc	Tenting included for project location			
			Total	\$65,000.00