

PROPOSAL

HBRK Associates Inc.
575 Lexington Avenue 4th Floor
New York, NY 10022
tel 212-971-1306
fax 212-320-0381

August 23, 2018

Re: Little St. James

Install Description:

Bag off and protect adjacent areas as necessary. Remove and discard water damage flooring in the cabana 2 bathroom. Supply and deliver Hakwood's 3/4" x 7" engineered, *unfinished*, prime grade European Oak in random lengths (6'-8'). Adhere a 90 mil membrane, which reduces moisture vapor transmission, water intrusion and sound reduction, to the concrete subfloor. Mechanically fasten a 3/4" CDX plywood to the membrane covered concrete subfloor. Adhere Oak plank to the plywood subfloor. Room to be covered is the pool cabana office and cabana 2 bathroom.

Bag off and protect adjacent areas as necessary. Sand Oak plank coarse, medium and fine as necessary, stain to match approved sample and finish with commercial grade urethane. Rooms to be covered include the cabana 2 bedroom and bathroom and the pool cabana office. At owner's discretion, damaged boards are to be replaced on a time and materials basis. We assume the wear layer is sufficient to sand.

Job Estimate:

Rooms	Estimate *
Pool Cabana Office	\$26,690.00
Cabana 2 Bathroom	\$6,050.00
Cabana 2 Bedroom	\$5,330.00

Notations:

1. * Includes labor and material
2. We assume the subfloor provided for us to be smooth, flat to meet industry tolerances of 1/4" variance over a 10' span, clean and dry. Any flattening of subfloor to be done on a time and materials basis.
3. Finished floor height is proposed to be 1 3/4" from a flat/level substrate.
4. Customer understands and accepts that there may be a visible difference in color tone and sheen level between newly refinished flooring and existing flooring
5. Furniture, furnishings, appliances, etc. to be removed by others prior to start date.
6. We assume the wear layer is sufficient to sand.
7. It is recommended that the baseboards, casings, and/or plinth blocks be installed after the flooring.
8. Although AHF will use reasonable and prudent measures to limit wood dust, it will be necessary for a final dust clean-up after our scope of work.
9. Although AHF will be careful not to damage any of the adjacent painted surfaces, it is likely that there will be some required touch-up painting after our scope of work.
10. Due to the availability of the flooring material, estimate is valid for 30 days. After 30 days, estimate is subject to change.
11. Proposal does not include any permit fees or security deposits.
12. Failure to pay complete contract total voids all warranties i.e. (all warranties expressed or implied).
13. No weekend/holiday work is included in contract price. If weekend/holiday work is required, there will be a schedule expedition charge to be added on an hourly basis.



Signature of Representative