

# PAVER & MARBLE

Professionals

Est. 1994

201 W. Ocean Ave #3828, Lantana FL 33465

[www.PaversandMarble.com](http://www.PaversandMarble.com)

Install / Repair  Clean / Seal

 POWERWASHING PROFESSIONALS

## Work Plan & Agreement

Jim - Direct #: [REDACTED] FRONT ENTRANCE / EL BRILLO

Date: October 23, 2018	E-Mail: [REDACTED]
Phone: 347-549-2291 Office Rich: 917-414-7584	Subdivision:
Customer Name: Jeff Epstein Property Mgr. Name: Carluz Toylo	Address: 358 Brillo Way Palm Beach, FL 33480

<input type="checkbox"/> Driveway	<input type="checkbox"/> Pool Area	<input type="checkbox"/> Walkway	<input type="checkbox"/> Patio
-----------------------------------	------------------------------------	----------------------------------	--------------------------------

Other: Front Entrance Steps / El Brillo

Service / Product	Est. Sq. Ft. / Size	Product Type
REMOVE EXISTING RE-BUILD AND EXTEND		WHITE FOSSIL 24 X 24 AND 8 X 16
ELIMINATE 1 STEP BOTTOM STEP APPROX. 16 FT WIDE		

- |   |  |   |
|---|--|---|
| <input checked="" type="checkbox"/> Installations / Extensions              | <input checked="" type="checkbox"/> Road Rock Base Material 2 Ton              | <input checked="" type="checkbox"/> Apply Sealer per Manufacture Spec |
| <input checked="" type="checkbox"/> Repair / Lift and Reset Areas Discussed | <input type="checkbox"/> Root Clearing   | <input checked="" type="checkbox"/> Apply with Airless Spray Guns     |
| <input type="checkbox"/> Sand Spaces Where and When Needed                  | <input checked="" type="checkbox"/> Extra Chemical / Detergent Used for Stains | <input type="checkbox"/> Xylene Base Acrylic Brick/Cement             |
| <input type="checkbox"/> Pool Remodel / Coping & Tile                       | <input checked="" type="checkbox"/> Work Completed to ICPI and Florida Code    | <input checked="" type="checkbox"/> Water Base Acrylic Marble/Stone   |
| <input type="checkbox"/> Retaining Wall Cement Block                        | <input checked="" type="checkbox"/> Hot Water / Steam Clean All Surfaces       | <input type="checkbox"/> DOT Approved Filter Fabric                   |
| <input type="checkbox"/> Drainage Field Created                             | <input type="checkbox"/> Strip Bad Sealer (No Guarantees)                      | <input type="checkbox"/> Silica Polymer Sand ___ Lbs.                 |
| <input checked="" type="checkbox"/> Excavate As Needed                      | <input type="checkbox"/> Tinted Sealer Per Cust. Auth./Color Approval          | <input checked="" type="checkbox"/> Crushed Silica 800 Lbs.           |

Items	Description	Amount
1	EXCAVATE EXISTING CONCRETE AT FOOT OF STEPS, AND STEPS (SEE PHOTOS)	
2	RE-BUILD EXISTING STEPS AND ELIMINATE SMALL STEP AT TOP	
3	EXTEND THRESHOLD LEVEL TO EXISTING AND CONVERT 4 STEPS TO 3 EXTENDED STEPS FOR ENTRANCE	
4	INSTALL DRAINAGE ROCK BASE AND MACHINE COMPACT 90 PSI	
5	INSTALL AGGREGATE FOR ALL NEW EXTENDED STEPS	
6	INSTALL 24 X 24 WHITE FOSSIL MARBLE WITH POLISED BULLNOSE EDGE (MATERIALS)	\$3,100
7	BOTTOM STEP TO EXTEND EVEN WITH LEFT AND RIGHT RETAINING WALL WITH BOTTOM THRESHOLD MEETING EXISTING DRIVE WITH REMOVAL OF (4) 48 X 48 CONCRETE	
	DEMO AND REMOVAL OF EXISTING	\$1,750
	BUILD NEW STEPS WITH POLISHED BULLNOSE EDGING	\$6,600
	POWER WASH, CLEAN, GROUT ALL SEAMS AND SEAL	\$900
<b>TOTAL</b>		<b>\$12,350</b>

- Customer is responsible to move all furniture and items including pool fences before start date
- All Installations / Repairs and Sealing - 2 Year Warranty - Workmanship & Repairs - Warranty upon completion**
- Brick / Marble ordered may have efflorescence or imperfections. Manufacturers' specifications & warranties accepted by Customer
- New Brick or Marble ordered will be matched to the existing surfaces to the best of our ability
- Powerwashing Professionals is not responsible for dirt in pool from cleaning, or broken sprinkler / electrical lines
- Stains will be treated and removed 25% - 100% - No guarantee
- Permitting, underground piping, water lines, etc. that are unknown, may require additional work and charges.**
- A deposit of \$2,500 is required to place on work schedule. Balance due day of completion.

### Agreement & Scheduling

Email: [paversandmarble@comcast.net](mailto:paversandmarble@comcast.net)

Deposit Check #	Amount:	Date:
Paver & Marble Professionals is Authorized for the work described.		The above conditions, specifications and prices Accepted.
Paver & Marble Signature: Jim Bird		Customer Signature:





