

Three B's LLC
4900 - A Jefferson
Albuquerque, M 87109

Brice Gordon
Zorro Ranch
Stanley, NM

Re: Septic drain

Brice,
Here is a price for th above referenced project

Remove pavers
Remove gravel and stockpile
Dig down to existing cast iron pipe
Cut cast iron pipe and remove (approximately 30 feet)
Remove clean outs (2)
Intall new sanitary PVC pipe and couplings
Install new clean outs (2)
Fill with dirt, compact
Fill with gravel
Place pavers

We are unable to see the entire pipe and any unforeseen damage that need to be repaired will result in a change order, upon your approval.
Price \$ 2,200.00 plus tax

If you have any question, please call me at [REDACTED]

Thank you,

JJ Blea, Managing Partner

E. C. BASSETT CONST., INC.
NM Lic. #033357
34 Highway 344 North P.O. Box 100
EDGEWOOD, NM 87015-0100

JOB ESTIMATE

(505) 281-3155 FAX (505) 281-2227

PHONE

DATE

8-4-2013

JOB NAME/LOCATION

OLD House AT Ranch

Head Quarters

TO Grace Zorra Ranch
P.O. Box 576
Stanley NM

JOB DESCRIPTION:

> Replace Main Sewer line from
App 2'-4' From OLD House Wall To The
CLEANOUTS. Install New CLEANOUTS App 4'
From The Old House Wall And Install New
3" or 4" SCH 40 PVC Pipe.

#

3500.00

Tax 6.875

240.63

3740.63

All Utilities Need To Be MARKed

> All Rocks Need To Be Removed App 20' wide
Do Be Able To Dig with A Backhoe

THIS ESTIMATE IS FOR COMPLETING THE JOB AS DESCRIBED ABOVE.
IT IS BASED ON OUR EVALUATION AND DOES NOT INCLUDE MATERIAL
PRICE INCREASES OR ADDITIONAL LABOR AND MATERIALS WHICH
MAY BE REQUIRED SHOULD UNFORESEEN PROBLEMS OR ADVERSE
WEATHER CONDITIONS ARISE AFTER THE WORK HAS STARTED.

ESTIMATED
JOB COST

3740.63

ESTIMATED
BY

E. C. Bassett