

RMC Electric-Randy Morales
P O Box 10645
Albuquerque NM 87184
Phone: 505-342-0800
Fax: 505-342-0811
Estimate/Bid
June 18, 2012

Attn: Brice
To: Zorro Ranch
Job: Well K Estimate

1) 300ft of 2" PVC	202.00
2) 2-2" LB 20/ea	40.00
3) 1- 2 pole, 100 amp breaker	150.00
4) 1- 100 amp main breaker indoor panel	200.00
5) 3- 300ft runs of 1/0 copper Thhn wire	2,750.00
6) 1- 300ft run #2 copper Thhn ground	360.00
7) Miscellaneous fittings	250.00
Materials	3,952.00
Labor	3,560.00

\$7,512.00

Note:

- 1) Digging for 100amp circuit from meter to well is excluded from price
- 2) Well control wiring not included in price

Option 1) If 480volt, 3 phase motor is used, add this amount to above price

20HP 3 sub add-a-phase 9,300.00

Labor & materials to install 900.00

Must be within 10ft of well motor starter

Freight cost will be added to price and is to be determined

Option 2) 480 Volt single phase

1) One 250 amp, 480 volt single phase panel	300.00
2) One 250 amp main breaker kit	260.00
3) One 75KVAA step up transformer 240 to 480	3,050.00
4) Miscellaneous material to install transformer and connect to well motor starter	390.00
5) Labor to install and connect	900.00

Change orders will apply if extra work is needed varying from the above stated.

Any alteration or deviation from the above specifications will involve extra costs and written order and will become an extra charge over and above the estimate. All agreements are contingent upon anything beyond our control

Acceptance of Proposal

*The above prices, specification and conditions are satisfactory and are hereby accepted. RMC Electric is authorized to do the work as specified.*Date: _____ Signature: _____

Thank you -Randy Morales-