

3B's LLC
4600 Lincoln rd. NE
Albuquerque, NM 87109
232-9494

Brice,

Here is a price to replace the limestone on the terrace with new limestone (north), and place a colored concrete (east).

Remove existing limestone from deck(s)

I will use a lift to get the pieces down from the deck safely and efficiently

Apply primer

Pump mix, 3/8", 4000 psi, colored concrete mix design with fiber. Up to 4" thick.

We will have a pump on site to place the concrete

After full cure we will seal the concrete

Install new limestone on north terrace

Clean area

\$ 43,535.00 plus tax

Materials

New limestone 9,335.00 (125 pieces, 1 1/4") + owner provided limestone (150)

New concrete 3000.00

Pump 1000.00

Sealer 400.00

Curing agent 200.00

Lift 2000.00

Labor

Supervision 1500.00

Demo 5 guys 6 days 4800.00

Prep for concrete 2 guys 1 day 350.00

Concrete placement 8 guys 2 days 2400.00

Installation on new limestone 9000.00

Cleanup 2 guys 2 days 350.00

Travel for entire Job 11 days 1000.00

Work comp 2500.00

Plus markup 4700.00

Score lines into concrete, in diamond pattern

Concrete is concrete and more times than not, cracks.

I am not sure how to repair the leak on the east terrace without removing the existing tile, and bed of cement on which the limestone is placed and installing a new membrane.

That is something we can address more in depth through correspondence.

Let me know what you think

Please call me if you have any questions at [REDACTED].

Thank you,

JJ Blea