



**LES FILE DRYWALL, INC.**

116 INDUSTRIAL NE ALBUQUERQUE, NEW MEXICO 87107  
 (505) 345-8283 FAX (505) 345-7528

NM License [REDACTED]  
 NM Dept. of Labor Registration # 000224930784  
 Page 1 of 2

Bid: ZORRO Ranch site wall stucco	Date: 04/12/10
Attn: Estimating Department	Plan Date:
Addendum: 0	Contact: Alan Chavez

Remove existing gypsum board at pilaster pop out detail and remove loose/peeling stucco finish and place in appropriate dump trailer provided by ZORRO Ranch for disposal.
Install weep screed at bottom of wall to be re-stuccoed, install all plaster stops/casing beads at pilasters to create new pop outs and at dissimilar materials.
Install new weather barrier and expanded metal lath and install a new 2coat cement stucco system, apply a new fiberglass mesh over stucco system with a synthetic base coat, apply a new "Acrylic" based finish coat over base coat.
Apply a color wash over new finish coat to achieve a Faux finish
Install sealants at casing beads to dissimilar surfaces

Job Specific Inclusions:

Job Specific Exclusions:

Standard Exclusions:

Customer to pay NM gross receipts tax on price

**\$ 69,600.00**

Bid		
	NM Gross Receipts Tax- Santa Fe County	6.50% \$ 4,524.00
	Add options:	
	Add for re-stucco at Mechanical House	\$ 43,000.00
	tax	\$ 2,795.00
	<b>Total Mechanical</b>	<b>\$ 45,795.00</b>
*****	ADD FOR BOND NOT INCLUDED IN BASE BID	1.03% \$ 720.00
	<b>PROPOSAL VALID FOR 60 DAYS</b>	
	MATERIAL QUOTES GOOD THROUGH 4TH QTR. 2010. MUST BE NOTIFIED WITHIN 30 DAYS OF BID DATE TO SECURE MATERIAL QUOTES	