



PROPOSAL

TO:
BRICE GORDON

PHONE:
[REDACTED]

DATE:
12/12/18

[REDACTED]

JOB NAME/LOCATION:
Brice Gordon

[REDACTED]

JOB NUMBER:

JOB PHONE:

Air Pro Inc. will provide labor and materials for the following work:

- Remove and dispose of the existing swamp cooler
- Cap and seal the existing swamp cooler supply duct with an insulated sheet metal cap
- Furnish and install one new Carrier 3 ton/16 SEER/single stage A/C split system with a new single stage/80% AFUE furnace, furnace model #58DLA090-114, coil model #CNPVP3617ALA, condenser model #24APB636A003
- Fabricate and install a new sheet metal transition to tie into the existing supply air plenum
- Fabricate and install a new filter rack stand to set the new coil and furnace on and tie into the existing return air plenum
- Tie into the existing gas supply line with all new connections, including the addition of a sediment trap as required by code
- Tie into the existing electrical for the furnace with all new connections, including hardwiring the furnace to a switch as required by code
- Install a new digital programmable Carrier Edge thermostat
- Run all new double wall flue vent piping for the furnace and bring up to current code standards
- Set condenser on a new equipment pad on the south side of the house, ground level
- Run line-set (refrigeration piping) from the evaporator coil to the condenser through the exterior wall of the mechanical closet and exposed outside along the soffit
- Run a gravity condensate line to the outdoors through the exterior wall of the mechanical closet
- Complete system check and start-up, including derating the furnace for altitude and setting R410A refrigerant levels to the manufacturers specifications
- Permit fees and inspections

Sub Total \$9,483.38
 Tax \$746.82
 Total \$10,230.20

Notes:

- *Any/all high voltage electrical circuits for the new condensers are to be provided by others
- *Skytrac lift for removing the swamp cooler is to be provided by others
- *Condenser unit is to come equipped with a compressor sound blanket and condenser coil hail guards for unit protection

We propose hereby to furnish material and labor-complete in accordance with the above specifications, for the sum
Dollars \$10,230.20

Payment to be made as follows:

MATERIALS AND EQUIPMENT REMAIN PROPERTY OF AIR PRO, INC. UNTIL PAID FOR IN FULL.

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents, or delays beyond our control. Owner to carry fire, tornado, and other necessary insurances. Our workers are fully covered by Worker's Compensation insurance.

Authorized Signature: _____

Note: This proposal may be withdrawn by us if not accepted within _____ days.

Acceptance of Proposal –The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Signature: _____

Date of Acceptance: _____

Signature: _____