



INSTALL NEW RAILING - TOP RAIL TO BE ALUMINUM. DO NOT OBTAIN RAILING FROM EXISTING

REMOVE WINDOW; CUT MASONRY DOWN TO FLOOR LEVEL. INSTALL NEW WOOD DOORS. MODIFY OR REPLACE EXISTING PARTITION AS SHOWN

**GENERAL NOTES**

1. BATHS #2 & #3 TO BE FINISHED WITH MARBLE TILE ON FLOOR & WALLS. FILL HOLLOW CONCRETE BLOCKS TO BE 3/4" CLEAR. CEILING TO BE PAINTED WHITE.
2. BATHS #4 & #5 TO BE FINISHED WITH MARBLE TILE ON WALLS. BATH #4 TO BE 3/4" CLEAR. FLOOR TO BE CARPET. CEILING TO BE PAINTED WHITE. DO NOT CUT THROUGH WALLS (CHECK FOR HANGING CEILING).
3. INSTALL NEW CROWN MOULDING IN GUEST ROOMS #1, #2 & #3.
4. INSTALL NEW DOORS, FINISHED & CASING MARKED.
5. INSTALL NEW G.W.P. - BATHS #2, #3, #4, #5.
6. A.C. SYSTEM CONTRACTOR SHALL PROVIDE WIRE PANS FOR HANGING TO A.C. SYSTEM. WEIGHT SHALL BE PERMITTED.



**EPSTEIN RESIDENCE**

358 El Brillo Way  
Palm Beach, Florida

**ROGER WM. SAHLI ARCHITECT**

15 EAST 78 STREET  
NEW YORK, NEW YORK  
10021  
TEL 212 439 3094  
FAX 212 439 9104

**MICHAEL J. BRINSON ARCHITECT**

410 GARDEN AVENUE  
WEST PALM BEACH, FLA.  
33411-3000

NO	DESCRIPTION	DATE

NO DESCRIPTION IN REVISIONS  
DRAWING TITLE  
**SECOND FLOOR PLAN**  
SCALE 1/4" = 1'-0"  
DATE 4-7-74  
PROJECT NO. 7  
DRAWING NO. A-2